BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OWN/WORK_INDENT54316

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/18/2022-23, Date: 04-11-2022

Name of Work:Improvements to Roads and drain at Rachenahalli, Srirampura and Nagawara Colony in Ward No.08 Jakkur.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M N RAMAIAH ( )	
				In Figures	In Words
1	941.65	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.	Cum	214.00	Rupees Two Hundred Fourteen Only
2	156.52	Providing and laying in position plain cement concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications.	Cum	6392.00	Rupees Six Thousand Three Hundred Ninety Two Only
3	302.96	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately)	Cum	7211.00	Rupees Seven Thousand Two Hundred Eleven Only
4	18.73	Supplying, Fitting and Placing TMT Fe550 bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.	Tonne	106071.00	Rupees One Hundred Six Thousand Seventy One Only
5	812.52	Providing and Fixing pre cast covering Slab 100mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge.	Sqm	2168.00	Rupees Two Thousand One Hundred Sixty Eight Only
6	43.20	Providing and Fixing pre cast covering Slab 230mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge.	Sqm	5270.00	Rupees Five Thousand Two Hundred Seventy Only
7	941.65	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3)	Cum	136.00	Rupees One Hundred Thirty Six Only
8	1205.31	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km	T.km	110.00	Rupees One Hundred Ten Only

M N Ramaiah.

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92